



SECTION

- | | |
|--|---|
| <ol style="list-style-type: none"> 1. AMETEK OR EQUAL PLASTIC VALVE BOX WITH BOLT DOWN LID. 2. FINISH GRADE 1" BELOW LID. 3. UL LISTED WATERPROOF CONNECTORS. 4. COILS: LEAVE EXCESS 2'-0" COILS IN EACH VALVE BOX. WRAP WIRE AROUND 1/2" PIPE 15 TIMES TO CREATE COILS. | <ol style="list-style-type: none"> 5. 3" LAYER OF PEA GRAVEL. 6. CONTROL WIRE FROM CONTROLLER. 7. COMMON WIRES. 8. SCHEDULE 80 PVC NIPPLE. 9. PVC MAIN LINE. 10. PVC UNION. 11. PVC LATERAL TO SPRINKLER HEADS. 12. ALL WIRE TO BE INSTALLED AS PER LOCAL CODE. |
|--|---|



STANDARD DETAILS
REMOTE CONTROL VALVE

COTTAGE GROVE, MINNESOTA

JANUARY 2021

PLATE NO.
IRR-5